



PIPE NOMINAL DIA.	CUBIC FT. OF CONCRETE REQUIRED PER 100 P.S.I. PRESSURE *		
	45°	22 1/2°	11 1/4°
4	7	4	2
6	15	8	4
8	27	14	7
10	* *	21	11
12	* *	* *	16

- * INCREASE VOLUMES SHOWN IN PROPORTION TO PRESSURES EXISTING WHEN PRESSURE TESTING PIPELINE.
- * * SPECIAL DESIGN REQUIRED.

APPROVED:
 5/16/19
 District Engineer Date
 5/16/2019
 Latest Revision Date

VALLEY CENTER MUNICIPAL WATER DISTRICT
 STANDARD DRAWING

VERTICAL ANCHOR BLOCK

NOT TO SCALE

DWG. NUMBER
W-27