

SECTION 01505
MOBILIZATION / DEMOBILIZATION

PART 1 - GENERAL

1.01 GENERAL

A. Mobilization shall include the acquisition of all permits; moving onto the site of all plant and equipment; furnishing and erecting plants, temporary buildings, and other construction facilities; and implementing security requirements; all as required for the proper performance and completion of the Work. Mobilization shall include but not be limited to the following principal items:

1. Moving on to the site of all CONTRACTOR'S plant and equipment required for construction operations.
2. Installing temporary construction power, wiring, and lighting facilities.
3. Establishing fire protection system.
4. Developing construction water supply as required.
5. Providing field office trailer for the CONTRACTOR (at CONTRACTOR'S option).
6. Providing all on-site communication facilities, including telephones and radios for CONTRACTOR personnel.
7. Providing on-site sanitary facilities and potable water facilities for CONTRACTOR personnel.
8. Arranging for and establishment of, CONTRACTOR'S storage yard as required. (CONTRACTOR is solely responsible for obtaining property owner agreements to use private property for storage or laydown areas per the contract documents.)
9. Constructing and implementing security features and requirements in compliance with the Contract Documents.
10. Obtaining all required permits.
11. Having all OSHA required notices and establishment of safety programs.
12. Submitting initial submittals.
13. Bonds
14. Insurance

1.02 CONSTRUCTION FACILITIES PLAN

A. Prior to commencement of any field work, the CONTRACTOR shall submit a Construction Facilities Plan to the Owner's Representative for approval. Said plan shall show the layout, equipment, materials and procedures the CONTRACTOR proposes for construction of temporary electrical, telephone, lighting, heating, water, sanitation, field offices and sheds, and other similar site facilities.

B. The CONTRACTOR'S site office and other construction facilities shall be of a temporary nature. The CONTRACTOR shall be wholly responsible for the security of his site office and laydown area, and for all its plant, materials, equipment and tools at all times.

1.03 DEMOBILIZATION

A. At the completion of the project, the CONTRACTOR shall perform the following activities:

1. Remove and properly dispose of all excess or waste materials, debris, rubbish, and temporary facilities from the site, structures and all facilities.
2. Repair pavement, roads, landscaping, and all other areas affected by construction operations and restore them to original condition or to a minimum condition specified.
3. Remove spatter, grease, stains, fingerprints, dirt, dust, labels, tags, packing materials, and other foreign items or substances from interior and exterior surfaces, equipment, signs, and lettering.
4. Repair, patch, and touch up chipped, scratched, dented or otherwise marred surfaces to match specified finish.
5. Remove paint, clean and restore all equipment and material nameplates, labels and other identification markings.
6. Clean all slabs, pavements and ground surfaces
7. Provide the District with a signed release form(s) from all private property owners for whom any agreements for offsite staging and laydown areas that were secured specifically for this project

PART 2 – PRODUCTS

Not Used.

PART 3 – EXECUTION

Not Used.

END OF SECTION 01505